

**MURRAY LOGAN CONSTRUCTION, LLC.**

**General Contractors**

313 65th Trail North  
West Palm Beach, FL. 33413  
TELEPHONE 561-686-3948  
FAX 561-686-7465

**Change Order Request # 03**

DATE: March 19, 2024

TO: Town of Palm Beach  
951 Okeechobee Rd  
West Palm Beach, FL 33401

PROJECT: Town of Palm Beach: D-8 / E-5 Pump Station Improvements

COR: Remove and Replace Wafer Check Valves

The Town has requested that Murray Logan Construction provide them with a cost estimate to remove the four existing wafer check valves, 3ea-36" and 1ea-12", at the D-8 Pump Station and replace them with new 316 stainless steel wafer check valves with Inconel X-750 springs.

1. Remove and install 3ea 36" wafer check valves and 1ea 12" wafer check valve:  
\$53,285.00
2. Furnish 3ea new 36" wafer check valves, 1ea new 12" wafer check valve and spare springs sets for each size wafer check valves:  
\$246,978.82

**Total:** \$300,263.82

Option 1: Rehabilitate existing manatee grate: \$2,630.00  
Option 2: Fabricate new 316 stainless steel manatee grate: \$3,375.00

Notes:

1. Price quoted includes 1ea set of spare springs for the 36" wafer check valves and 1ea set of spare springs for the 12" wafer check valve. Springs shall be constructed from Inconel X-750 steel.
2. Price quoted for Options 1 and 2 are for the manatee grates and do not include the removal or installation, as this cost is part of the base bid.

**ACCEPTED:**

**MURRAY LOGAN CONSTRUCTION, LLC.**

By: \_\_\_\_\_

By: Kurt Kapsos

Date: \_\_\_\_\_

Title: Kurt Kapsos, Vice President



## Bid Proposal for MURRAY LOGAN D-8 PUMP STATION CHECK VALVES

**MURRAY LOGAN CONSTRUCTION INC**

**Job Location:** Palm Beach, FL

**Bid Date:** 03/15/2023

**Core & Main** 3420243

**Core & Main**

1101 W 17th St

Riviera Beach, FL 33404

**Phone:** 5618484396

**Fax:** 5618457267

Seq#	Qty	Description	Units	Price	Ext Price
10	3	36" 316SS WAFER CHECK VLV 36-31R-44ESX15 METAL HINGE, 316 INTERNALS SERIES-31R, WAFER, 316SS, EPDM X-750 INCONEL SPRINGS, 150 PSI	EA	64,985.00	194,955.00
70	1	36" INCONEL X-750 SPRING SET FIGURE 36-31R-44ESX15	EA	4,275.00	4,275.00
110	1	12" 316SS WAFER CHECK VLV 12-31R-44ESX15 METAL HINGE, 316 INTERNALS SERIES-31R, WAFER, 316SS, EPDM X-750 INCONEL SPRINGS, 150 PSI	EA	10,528.00	10,528.00
170	1	12" INCONEL X-750 SPRING SET FIGURE 12-31R-44ESX15	EA	2,012.00	2,012.00
				<b>Sub Total</b>	<b>211,770.00</b>
				<b>Tax</b>	<b>12,756.20</b>
				<b>Total</b>	<b>224,526.20</b>

UNLESS OTHERWISE SPECIFIED HEREIN, PRICES QUOTED ARE VALID IF ACCEPTED BY CUSTOMER AND PRODUCTS ARE RELEASED BY CUSTOMER FOR MANUFACTURE WITHIN THIRTY (30) CALENDAR DAYS FROM THE DATE OF THIS QUOTATION. CORE & MAIN LP RESERVES THE RIGHT TO INCREASE PRICES TO ADDRESS FACTORS, INCLUDING BUT NOT LIMITED TO, GOVERNMENT REGULATIONS, TARIFFS, TRANSPORTATION, FUEL AND RAW MATERIAL COSTS. DELIVERY WILL COMMENCE BASED UPON MANUFACTURER LEAD TIMES. ANY MATERIAL DELIVERIES DELAYED BEYOND MANUFACTURER LEAD TIMES MAY BE SUBJECT TO PRICE INCREASES AND/OR APPLICABLE STORAGE FEES. THIS BID PROPOSAL IS CONTINGENT UPON BUYER'S ACCEPTANCE OF SELLER'S TERMS AND CONDITIONS OF SALE, AS MODIFIED FROM TIME TO TIME, WHICH CAN BE FOUND AT: <https://coreandmain.com/TandC/>

Cost break down:

Cost of materials, including tax: \$224,526.20

10% Contractor's markup: \$22,452.62  
=====

Total Mat'l cost: \$246,978.82