
RECEIVED

By yfigueroa at 8:06 am, May 06, 2024

CURRENTLY PROPOSED

235 Banyan Road
Town of Palm Beach
COA 23-43
ZON-23-117



Site Plan-Limits of Work

SCALE: 1/32" = 1'



FOUNTAIN BUBBLER






CENTRAL FOUNTAIN INSPIRATION




ANTIQUE TERRA COTTA TILE



48 HOURS BEFORE DIGGING
CALL TOLL FREE






Proposed Site Data

DESCRIPTION	REQUIRED		PROPOSED	
LOT ZONE			R-A - ESTATE RESIDENTIAL	
LOT AREA	20,000 S.F.	MINIMUM	31,119.66 S.F.	
OPEN / PERMEABLE SPACE	MINIMUM 50%	15,559.83 S.F.	50.3%	15,655 S.F.
FRONT YARD LANDSCAPE	MINIMUM 45% OF FRONT YARD	3,802.45 S.F.	76%	5,471 S.F.


COA 23-43 ZOM-23-117 Site Plan SCALE IN FEET: 3/16"=1'-0"

DE/IG/I 3 ROUP 139 North County Road S#20−B Palm Beach, FI 33480 Phone 561.832.4600 Mobile 561.313.4424 Landscape Architecture Land Planning Landscape Management Dustin M. Mizell, MLA RLA #6666784 Dustin@environmentdesigngroup.com



JOB NUMBER: # 23107.00 LA DRAWN BY: Lauren Freeman DATE: 10.05.2023


/HEET L5.0



Existing Open Space Graphic

Existing Site Data

DESCRIPTION	REQUIRED		EXISTING	
LOT ZONE			R-A - ESTATE RESIDENTIAL	
LOT AREA	20,000 S.F. MINIMUM		31,11	19.66 S.F.
OPEN / PERMEABLE SPACE	MINIMUM 50%	15,559.83 S.F.	52.93%	16,471.87 S.F.
FRONT YARD LANDSCAPE	MINIMUM 45% OF FRONT YARD	3,802.45 S.F.	87.81%	6,071.15 S.F.



Proposed Open Space Graphic

Proposed Site Data

DESCRIPTION	REQUIRED		PROPOSED	
LOT ZONE	R-A - ESTATE RESIDENTI		E RESIDENTIAL	
LOT AREA	20,000 S.F. MINIMUM		31,119.66 S.F.	
OPEN / PERMEABLE SPACE	MINIMUM 50%	15,559.83 S.F.	50.3%	15,655 S.F.
FRONT YARD LANDSCAPE	MINIMUM 45% OF FRONT YARD	3,802.45 S.F.	76%	5,471 S.F.

Legend

IMPERVIOUS AREA (HOUSE/STRUCTURE)

IMPERVIOUS AREA (HARDSCAPE) PERVIOUS AREA / OPEN SPACE

IMPERVIOUS AREA / WATER FEATURE

COA 23-43 ZOM-23-117

DE/IGM GROUP 139 North County Road S#20-B Palm Beach, FI 33480 Phone 561.832.4600 Mobile 561.313.4424 Landscape Architecture Land Planning Landscape Management

Dustin M. Mizell, MLA RLA #6666784 Dustin@environmentdesigngroup.com

JOB NUMBER: # 23107.00 LA
DRAWN BY: Lauren Freeman
DATE: 03.11.2024

/HEET L5.1

COPYRIGHT:


The following drawings are instruments of service to the Landscape Architect. They are not products of design. All ideas, designs, arrangements and plans indicated or represented by this/these drawings are owned by and the property of the designer, and were created, evolved and developed for use on and in connection with this project. None of such ideas, designs, arrangements or plans shall be used by or disclosed to any person, firm or corporation without the written permission of the Landscape Architect.

DISCLAIMER:


Construction, as the term is generally understood, and that ENVIRONMENT DESIGN GROUP does not provide landscape architectural services during construction, including on—site monitoring, site visits, shop drawing review, design clarification, etc., the client agrees to indemnify and hold harmless ENVIRONMENT DESIGN GROUP from any liability arising from, acts or omissions in the performance of said services during construction by the client, and his/her agents, employees, or subcontractors.

48 HOURS BEFORE DIGGING CALL TOLL FREE 1-800-432-4770

Site Calculation / Open Space Graphics SCALE IN FEET: 1/16"=1'-0"



SCALE: 1/32" = 1





COA 23-43 ZOM-23-117Landscape Plan

SCALE IN FEET: 3/16"=1'-0"

JE/IG/I ROUP 139 North County Road S#20−B Palm Beach, FI 33480 Phone 561.832.4600 Mobile 561.313.4424 Landscape Architecture Land Planning Landscape Management Dustin M. Mizell, MLA RLA #6666784 Dustin@environmentdesigngroup.com

sid





/HEET L6.0

arrangements or plans shall be used by or disclosed to any person, firm or corporation without the written permission

of the Landscape Architect.

COPYRIGHT:

The following drawings are instruments of service to the Landscape Architect. They are not products of design. All ideas, designs, arrangements and plans indicated or represented by this/these drawings are owned by and the property of the designer, and were created, evolved and developed for use on and in connection with this project. None of such ideas, designs, arrangements or plans shall be used by or disclosed to any person firm.


DISCLAIMER:

2 0 2 4

Construction, as the term is generally understood, and that ENVIRONMENT DESIGN GROUP does not provide landscape architectural services during construction, including on—site monitoring, site visits, shop drawing review, design clarification, etc., the client agrees to indemnify and hold harmless ENVIRONMENT DESIGN GROUP from any liability arising from, acts or omissions in the performance services during the property of the designer, and were created, evolved and developed for use on and in connection with this project. None of such ideas, designs, arrangements or plans shall be used by or disclosed to any person firm. services during construction by the client, and his/her agents, employees, or subcontractors.


48 HOURS BEFORE DIGGING
CALL TOLL FREE 1-800-432-4770 SUNSHINE STATE ONE CALL OF FLORIDA, INC.






Site Plan-Limits of Work

SCALE: 1/32" = 1



DE/IG/I GROUP Landscape Architecture Land Planning Landscape Management Dustin M. Mizell, MLA RLA #6666784 Dustin@environmentdesigngroup.com



JOB NUMBER: # 23107.00 LA
DRAWN BY: Lauren Freeman

DATE: 12.07.2023
01.12.2024
02.26.2024
03.11.2024
04.29.2024
05.03.2024

SHEET L6.1

COPYRIGHT:

The following drawings are instruments of service to the Landscape Architect. They are not products of design. All ideas, designs, arrangements and plans indicated or represented by this/these drawings are owned by and the property of the designer, and were created, evolved and developed for use on and in connection with this project. None of such ideas, designs, arrangements or plans shall be used by or disclosed to any person, firm or corporation without the written permission of the Landscape Architect.

DISCLAIMER:

Construction, as the term is generally understood, and that ENVIRONMENT DESIGN GROUP does not provide landscape architectural services during construction, including on—site monitoring, site visits, shop drawing review, design clarification, etc., the client agrees to indemnify and hold harmless ENVIRONMENT DESIGN GROUP from any liability arising from, acts or omissions in the performance of said services during construction by the client, and his/her agents, employees, or subcontractors.

48 HOURS BEFORE DIGGING CALL TOLL FREE 1-800-432-4770

COA 23-43 ZOM-23-117 Rendered Site Plan
SCALE IN FEET: 3/16"=1'-0"

Trees

SYMBOL/KEY	PLANT NAME		QTY.	DESCRIPTION	NATIVE
(+)	BURSERA SIMARL GUMBO LIMBO T		1	15' X 15' - SPECIMEN	YES
(×)	COCCOLOBA DIVI PIGEON PLUM TE		3	16' HT.	YES
+	CONOCARPUS ER GREEN BUTTONI		2	12' HT., MATCHING	YES
+	CORDIA SEBESTE ORANGE GEIGER		2	8' HT.	NO
& X	LIGUSTRUM JAPONICUM LIGUSTRUM TREES		1	6'- HT.	NO
		TOTAL NATIVE SPECIES	9 6 (66.7%)		

Palms

SYMBOL/KEY	PLANT NAME	QTY.	DESCRIPTION	NATIVE
	PTYCHOSPERMA ELEGANS ALEXANDER PALMS	Ø15	8'-16' C.T. 8' C.T. MATCHING	NO
The state of the s	RHAPIS EXCELSA LADY PALM	80 80	25 GAL. 6' HT.	NO

Lawn & Mulch

AREA	PLANT NAME	QTY.	DESCRIPTION
LAWN MULCH	EMPIRE ZOYSIA LAWN EUCALYPTUS MULCH	AS NEEDED AS NEEDED	

Town of Palm Beach Planning Zoning and Building 360 S County Rd Palm Beach, FL 33480 www.townofpalmbeach.com

Line #	Landscape Legend						
1	Property Address: 235 Banyan Road						
2	Lot Area (sq. ft.): 31,119.66 S.F.						
3		REQUIRED PROPOSED					
4	Landscape Open Space (LOS) (Sq Ft and %)	15,559.83 S.F. (50%)	15,655 S.F. (50.3%)				
5	LOS to be altered (Sq FT and %)	N/A	2,020 S.F. (6.5%)				
6	Perimeter LOS (Sq Ft and %)	N/A	N/A				
7	Front Yard LOS (Sq Ft and %)	3,802.45 S.F. (45%)	5,471 S.F. (76%)				
8	Native Trees %	30%	67%				
9	Native Shrubs & Vines %	30%	69.6%				
10	Native Groundcover %	30%	43.8%				
To determine qualifying native vegetation use either:							

copyright:

The following drawings are instruments of service to the Landscape Architect. They are not products of design. All ideas, designs, arrangements and plans indicated or represented by this/these drawings are owned by and the property of the designer, and were created, evolved and developed for use on and in connection with this project. None of such ideas, designs, arrangements or plans shall be used by or disclosed to any person, firm or corporation without the written permission of the Landscape Architect.

48 HOURS BEFORE DIGGING CALL TOLL FREE 1-800-432-4770

Shrubs & Vines

SYMBOL/KEY	PLANT NAME	QTY.	DESCRIPTION	NATIVE
	AGAPANTHUS SPP BLUE AGAPANTHUS	5	3 GAL.	NO
	ANTHURIUM HOOKERI 'RUFFLES' BIRDS NEST FERN	4	7 GAL.	NO
	ASCLEPIAS TUBEROSA BUFFERFLY MILKWEED	20	3 GAL., 12" O.C.	YES
	ALOCASIA 'CALIFORNIA' DWARF ELEPHANT EAR	35	3 GAL.	NO
	BOUGAINVILLEA SPP BOUGAINVILLEA VINE	4	7 GAL., IN POTS ATTACH TO TRELLIS	NO
	CHRYSOBALANUS ICACO GREEN COCOPLUM	20	3 GAL., 12" O.C.	YES
	DIOON SPINULOSUM GIANT DIOON	1	15 GAL.	NO
	FARFUGIUM JAPONICUM 'GIGANTEA' GIANT LEOPARD PLANT	5	7 GAL.	NO
1 + 3	HAMELIA PATENS FIREBUSH	5	15 GAL.	YES
	MYRICA CERIFERA WAX MYRTLE HEDGE	48	4'-6' HT., 36" O.C.	YES
(X)	PSYCHOTRIA NERVOSA WILD COFFEE	24	7 GAL.	YES
5-2	STRELITZIA REGINAE ORANGE BIRD OF PARADISE	3	7 GAL.	NO
{ + }	THRYALLIS GRACILLIS YELLOW THRYALLIS	9	7 GAL.	NO
	ZAMIA INTEGRIFOLIA COONTIE	34	7 GAL.	YES
	TOTAL NATIVE SPECIES	217 151 (69.6%)		

Groundcovers


SYMBOL/KEY	PLANT NAME	QTY.	DESCRIPTION	NATIVE
	FICUS MICROCARPA GREEN ISLAND FICUS	35	3 GAL., 12" O.C.	NO
	HELIANTHUS DEBILIS DUNE SUNFLOWER	300	I GAL., 8" O.C.	YES
	MICROSORUM SCOLOPENDRIUM WART FERN	225	I GAL., 8" O.C.	NO
	PEPEROMIA OBTUSIFOLIA PEPEROMIA	50	I GAL., 8" O.C.	NO
	TRACHELOSPERMUM ASIATICUM JASMINE MINIMA	75	4" LINERS, 8" O.C.	NO
	TOTAL NATIVE SPECIES	685 300 (43.8%)		•

COA 23-43 ZOM-25-117Landscape/chedule



JOB NUMBER: 21089.00 LA
DRAWN BY: Lauren Freeman
DATE: 11.20.2023

SHEET L6.2





Coccoloba diversifolia PIGEON PLUM TREE



Cordia sebestena ORANGE GEIGER TREE




Alocasia 'California' DWARF ELEPHANT EAR



Ascelpias tuberosa
BUTTERFLY MILKWEED



Chrysobalanus icaco GREEN COCOPLUM




Hamelia patens FIREBUSH



Helianthus debilis DUNE SUNFLOWER



Thryallis gracillis



SHEET L6.3

COA 23-43 ZOM-23-117 Proposed Plant Images

COPYRIGHT:

The following drawings are instruments of service to the Landscape Architect. They are not products of design. All ideas, designs, arrangements and plans indicated or represented by this/these drawings are owned by and the property of the designer, and were created, evolved and developed for use on and in connection with this project. None of such ideas, designs, arrangements or plans shall be used by or disclosed to any person, firm or corporation without the written permission of the Landscape Architect.

DISCLAIMER:

2 0 2 4

Construction, as the term is generally understood, and that ENVIRONMENT DESIGN GROUP does not provide landscape architectural services during construction, including on—site monitoring, site visits, shop drawing review, design clarification, etc., the client agrees to indemnify and hold harmless ENVIRONMENT DESIGN GROUP from any liability arising from, acts or omissions in the performance of said services during construction by the client, and his/her agents, employees, or subcontractors.



ROUP

139 North County Road S#20-B Palm Beach, FI 33480 Phone 561.832.4600 Mobile 561.313.4424

Landscape Architecture Land Planning Landscape Management

Dustin M. Mizell, MLA RLA #6666784 Dustin@environmentdesigngroup.com



Bursera simaruba GUMBO LIMBO TREE



Zamia integrifolia



Ptychosperma elegans ALEXANDER PALMS



Ficus microcarpa & Jasmine GREEN ISLAND FICUS & JASMINE MINIMA



Conocarpus erectus


GREEN BUTTONWOOD TREES



Psychotria nervosa WILD COFFEE



Myrica cerifera
WAX MYRTLE HEDGE



139 North County Road S#20−B Palm Beach, Fl 33480 Phone 561.832.4600 Mobile 561.313.4424

Landscape Architecture Land Planning Landscape Management

Dustin M. Mizell, MLA RLA #6666784 Dustin@environmentdesigngroup.com

JOB NUMBER: 21089.00 LA
DRAWN BY: Lauren Freeman

DATE: 01.12.2024
02.26.2024
03.11.2024
04.29.2024
05.03.2024

SHEET L6.4

COPYRIGHT:

The following drawings are instruments of service to the Landscape Architect. They are not products of design. All ideas, designs, arrangements and plans indicated or represented by this/these drawings are owned by and the property of the designer, and were created, evolved and developed for use on and in connection with this project. None of such ideas, designs, arrangements or plans shall be used by or disclosed to any person, firm or corporation without the written permission of the Landscape Architect.

DISCLAIMER:

Construction, as the term is generally understood, and that ENVIRONMENT DESIGN GROUP does not provide landscape architectural services during construction, including on—site monitoring, site visits, shop drawing review, design clarification, etc., the client agrees to indemnify and hold harmless ENVIRONMENT DESIGN GROUP from any liability arising from, acts or omissions in the performance of said services during construction by the client, and his/her agents, employees, or subcontractors.

Farfugium japonicum 'Giganteum'

48 HOURS BEFORE DIGGING CALL TOLL FREE 1-800-432-4770

COA 23-43 ZOM-23-117Proposed Plant Images




Microsorum scolopendrium



Ligustrum japonicum LIGUSTRUM TREE



Anthurium hookeri 'Ruffles' BIRDS NEST FERN



Peperomia obtusifolia PEPEROMIA







Strelitzia reginae ORANGE BIRD OF PARADISE

COPYRIGHT:

The following drawings are instruments of service to the Landscape Architect. They are not products of design. All ideas, designs, arrangements and plans indicated or represented by this/these drawings are owned by and the property of the designer, and were created, evolved and developed for use on and in connection with this project. None of such ideas, designs, arrangements or plans shall be used by or disclosed to any person, firm or corporation without the written permission of the Landscape Architect.

DISCLAIMER:

Construction, as the term is generally understood, and that ENVIRONMENT DESIGN GROUP does not provide landscape architectural services during construction, including on—site monitoring, site visits, shop drawing review, design clarification, etc., the client agrees to indemnify and hold harmless ENVIRONMENT DESIGN GROUP from any liability arising from, acts or omissions in the performance of said services during construction by the client, and his/her agents, employees, or subcontractors.




48 HOURS BEFORE DIGGING
CALL TOLL FREE 1-800-432-4770 SUNSHINE STATE ONE CALL OF FLORIDA, INC.

Rhapis excelsa LADY PALMS



Agapanthus spp BLUE AGAPANTHUS

COA 23-43 ZOM-23-117 Proposed Plant Images



JOB NUMBER: 21089.00 LA
DRAWN BY: Lauren Freeman
DATE: 02.26.2024


139 North County Road S#20-B Palm Beach, FI 33480 Phone 561.832.4600 Mobile 561.313.4424

Landscape Architecture Land Planning Landscape Management

Dustin M. Mizell, MLA RLA #6666784 Dustin@environmentdesigngroup.com

PREVIOU/LY PRE/EMTED


235 Banyan Road
Town of Palm Beach
COA 23-43
ZON-23-117



Existing Open Space Graphic

Existing Site Data

DESCRIPTION	REQUIRED		EXISTING	
LOT ZONE			R-A - ESTATE	E RESIDENTIAL
LOT AREA	20,000 S.F. MINIMUM		31,1	19.66 S.F.
OPEN / PERMEABLE SPACE	MINIMUM 50%	15,559.83 S.F.	52.93%	16,471.87 S.F.
FRONT YARD LANDSCAPE	MINIMUM 45% OF FRONT YARD	3,802.45 S.F.	87.81%	6,071.15 S.F.



Proposed Open Space Graphic

Proposed Site Data

•				
DESCRIPTION	REQUIRED		PROPOSED	
LOT ZONE			R-A - ESTATE RESIDENTIA	
LOT AREA	20,000 S.F. MINIMUM		31,	119.66 S.F.
OPEN / PERMEABLE SPACE	MINIMUM 50%	15,559.83 S.F.	50.3%	15,655 S.F.
FRONT YARD LANDSCAPE	MINIMUM 45% OF FRONT YARD	3,802.45 S.F.	76%	5,471 S.F.

Legend

IMPERVIOUS AREA (HOUSE/STRUCTURE)

IMPERVIOUS AREA (HARDSCAPE)

PERVIOUS AREA / OPEN SPACE IMPERVIOUS AREA / WATER FEATURE

COA 23-43 ZOM-23-117

COPYRIGHT:

The following drawings are instruments of service to the Landscape Architect. They are not products of design. All ideas, designs, arrangements and plans indicated or represented by this/these drawings are owned by and the property of the designer, and were created, evolved and developed for use on and in connection with this project. None of such ideas, designs, arrangements or plans shall be used by or disclosed to any person, firm or corporation without the written permission of the Landscape Architect.


DISCLAIMER:

Construction, as the term is generally understood, and that ENVIRONMENT DESIGN GROUP does not provide landscape architectural services during construction, including on—site monitoring, site visits, shop drawing review, design clarification, etc., the client agrees to indemnify and hold harmless ENVIRONMENT DESIGN GROUP from any liability arising from, acts or omissions in the performance of said services during construction by the client, and his/her agents, employees, or subcontractors.

48 HOURS BEFORE DIGGING CALL TOLL FREE 1-800-432-4770







JOB NUMBER: # 23107.00 LA
DRAWN BY: Lauren Freeman
DATE: 03.11.2024

SHEET L5.1


DE/IG/I GROUP


139 North County Road S#20-B Palm Beach, FI 33480 Phone 561.832.4600 Mobile 561.313.4424

Landscape Architecture Land Planning

Landscape Management

Dustin M. Mizell, MLA RLA #6666784 Dustin@environmentdesigngroup.com





/HEET L1.0 COA 23-43

ZOM-23-117

JOB NUMBER: # 23107.00 LA
DRAWN BY: Aick Pastor
DATE: 10.05.2023

DE/IG/I ROUP

139 North County Road S#20-B Palm Beach, FI 33480 Phone 561.832.4600 Mobile 561.313.4424

Landscape Architecture Land Planning

Landscape Management

Dustin M. Mizell, MLA RLA #6666784 Dustin@environmentdesigngroup.com

bisclaimer:

Disclaimer:

Construction, as the term is generally understood, and that ENVIRONMENT DESIGN GROUP does not provide landscape architectural services during construction, including on—site monitoring, site visits, shop drawing review, design clarification, etc., the client agrees to indemnify and hold harmless ENVIRONMENT DESIGN GROUP for use on and in connection with this project. None of such ideas, designs, arrangements or plans shall be used by or disclosed to any person, firm or corporation without the written permission of the Landscape Architect.

48 HOURS BEFORE DIGGING

CALL TOLL FREE *1-800-432-4770* SUNSHINE STATE ONE CALL OF FLORIDA, INC.







Landscape Architecture Land Planning Landscape Management

Dustin M. Mizell, MLA RLA #6666784 Dustin@environmentdesigngroup.com

JOB NUMBER: # 23107.00 LA DRAWN BY: Mick Pastor DATE: 10.05.2023

/HEETL2.0

Existing West Buffer


Existing West Buffer

Existing West Buffer










Existing Garden Buffer

Existing Garden Buffer

COA 23-43 ZOM-23-117 Existing Conditions

Existing Garden Entry



Existing Pedestrian Entry

Existing South Buffer



COPYRIGHT:


The following drawings are instruments of service to the Landscape Architect. They are not products of design. All ideas, designs, arrangements and plans indicated or represented by this/these drawings are owned by and the property of the designer, and were created, evolved and developed for use on and in connection with this project. None of such ideas, designs, arrangements or plans shall be used by or disclosed to any person, firm or corporation without the written permission of the Landscape Architect.

DISCLAIMER:

2 0 2 4

Construction, as the term is generally understood, and that ENVIRONMENT DESIGN GROUP does not provide landscape architectural services during construction, including on—site monitoring, site visits, shop drawing review, design clarification, etc., the client agrees to indemnify and hold harmless ENVIRONMENT DESIGN GROUP from any liability arising from, acts or omissions in the performance of said services during construction by the client, and his/her agents, employees, or subcontractors.

48 HOURS BEFORE DIGGING CALL TOLL FREE 1-800-432-4770



Site Plan-Limits of Work

NOTE:
IF ANY INTERIOR SHRUBS, TREES AND PALMS
ARE REMOVED FOR SITE UTILIZATION AND
CONSTRUCTION DEVELOPMENT. A
CONSTRUCTION SCREEN WILL BE ADDED IN
THESE AREAS UNTIL NEW LANDSCAPING IS
INSTALLED. AT NO TIME SHALL THE SITE BE
OPEN TO ADJACENT PROPERTIES WITHOUT
ANY PERMANENT OR TEMPORARY SCREENING
DURING CONSTRUCTION DURING CONSTRUCTION.




EXISTING 20' HT. DENSE LANDSCAPE PRIVACY BUFFER NORTHWEST OF DRIVEWAY TO REMAIN



EXISTING 20' HT. DENSE LANDSCAPE PRIVACY BUFFER NORTHWEST OF DRIVEWAY TO REMAIN



EXISTING 20' HT. DENSE LANDSCAPE PRIVACY BUFFER SOUTHWEST OF DRIVEWAY TO REMAIN





EXISTING 20' HT. DENSE LANDSCAPE PRIVACY BUFFER EAST OF DRIVEWAY TO REMAIN



EXISTING 20' HT. DENSE LANDSCAPE PRIVACY BUFFER EAST OF DRIVEWAY TO REMAIN




EXISTING 20' HT. DENSE LANDSCAPE PRIVACY BUFFER SOUTHEAST OF DRIVEWAY TO REMAIN



EXISTING 20' HT. DENSE LANDSCAPE PRIVACY BUFFER SOUTHWEST OF DRIVEWAY TO REMAIN





DE/IG/I

Landscape Architecture

Landscape Management

Dustin M. Mizell, MLA RLA #6666784 Dustin@environmentdesigngroup.com

Land Planning

ROUP 139 North County Road S#20-B Palm Beach, FI 33481 Phone 561.832.4600 Mobile 561.313.4424

/HEET L3.0


256 sf.

Construction Screening & Staging Plan 2011-23-117

arrangements or plans shall be used by or disclosed to any person, firm or corporation without the written permission of the Landscape Architect.

COPYRIGHT:

The following drawings are instruments of service to the Landscape Architect. They are not products of design. All ideas, designs, arrangements and plans indicated or represented by this/these drawings are owned by and the property of the designer, and were created, evolved and developed for use on and in connection with this project. None of such ideas, designs, arrangements or plans shall be used by 48 HOURS BEFORE DIGGING
CALL TOLL FREE *1-800-432-4770* SUNSHINE STATE ONE CALL OF FLORIDA, INC. services during construction by the client, and his/her agents, employees, or subcontractors.



E AVIROAMEAT DE/IG/I ROUP 139 North County Road S#20-B Palm Beach, Fl 33481 Phone 561.832.4600 Mobile 561.313.4424 Landscape Architecture Land Planning Landscape Management Dustin M. Mizell, MLA RLA #6666784 Dustin@environmentdesigngroup.com

Residenc

PROPOSED TRUCK INGRESS / EGRESS ROUTES MAP

- SITE/BUILDING PREPARATION

- LANDSCAPE & HARDSCAPE

- FRONT FACADE IMPROVEMENTS

- PROPOSED TOTAL CONSTRUCTION

FOLLOWING BUILDING PERMIT

CONCEPTUAL CONSTRUCTION SCHEDULE

- FINISHES

INSTALLATION

– FINAL INSPECTIONS

• 1 MONTH -JUNE 2024 - MOBILIZATION & DEMOLITION

MAY 10, 2024 - LANDMARKS MEETING

MAY-JUNE 2024 - SUBMIT FOR PERMIT

SCHEDULE:

● 1-2 MONTHS

• 1-2 MONTHS

• <u>1-2 MONTHS</u>

• +/-10 MONTHS

4 MONTHS

• 2 MONTHS

MONTH 1: DEMOLITION AND CLEANUP (3 - 5 DAYS)

LARGEST TRUCK ->


10-15 DUMP TRUCKS FOR DEBRIS REMOVAL TRAILER FOR EXCAVATOR / DEMOLITION LANDSCAPE TRUCKS -> IRRIGATION


NOTE: SEE SEPARATE "CONSTRUCTION STAGING PLAN" SHEET FOR INFORMATION ON LOCATIONS FOR PARKING, MATERIAL STORAGE, DELIVERIES, DUMPSTER, PORTABLE TOILETS, TIRE CLEANING AREA, SILT FENCE, ETC.

PROPOSED INGRESS TRUCK ROUTE

PROPOSED EGRESS TRUCK ROUTE

COA 23-43 ZOM-23-117Truck Logistics Plan








COPYRIGHT:

The following drawings are instruments of service to the Landscape Architect. They are not products of design. All ideas, designs, arrangements and plans indicated or represented by this/these drawings are owned by and the property of the designer, and were created, evolved and developed for use on and in connection with this project. None of such ideas, designs, arrangements or plans shall be used by or disclosed to any person, firm or services during construction by the client, and his/her agents, employees, or subcontractors. or disclosed to any person, firm or corporation without the written permission of the Landscape Architect.

1-800-432-4770



Tree Planting

FILL MATERIAL SHALL CONSIST OF AT LEAST 1/3 NATIVE SOIL FROM THE HOLE DUG FOR THE PLANT. SEE SPECIFICATIONS FOR BACKFILL MIXTURE.

MASS. RETAIN THE NATURAL SHAP

BE DONE PRIOR TO INSTALLATION, APPROVAL, AND DIRECTION BY THE

USE 1/2" DIAM, REINFORCED RUBBER

WIRE: 3 (MIN.) EVENLY SPACED GUYS PER TREE, FOR TREES IO' AND OVER

ADD ONE TURNBUCKLE TO EACH WIRE TO MAINTAIN SUPPORT.

PRUNE LOWER BRANCHES AS PER

TOP OF BURLAP BALL SHALL BE AT LEAST I" ABOVE THE FINISHED GRADE.

B" MULCH LAYER (SHREDDED CYPRESS).

THE TREE PIT TO HOLD WATER

PREEN PAINT IS OPTIONAL).

COMPACTED EARTH.

WHITE FLAGGING RIBBON.

PRUNE ALL SHRUBS TO ACHIEVE A _ TOP OF BURLAP BALL SHALL BE AT LEAST I 1/2" ABOVE THE FIN. GRADE, - 3" MULCH LAYER (SHREDDED CYPRESS). BUILD 4"-6" CONTINUOUS SAUCER AROUND THE TREE PIT TO HOLD WATER. ROOT BALLS GREATER THAN 2-0" IN DIAM. SHALL SIT ON MOUND OF UNDISTURBED SOIL TO PREVENT SETTLING. ROOT BALLS SMALLER THAN 2'-O" DIAM. MAY SIT ON DIAMETER OF HOLE FOR BALL TO 2'-0' SHALL BE TWICE THE DIAMETER OF THE - ROOTBALL, DIAMETER OF THE HOLE FOR ROOTBALLS 2'-0' & GREATER SHALL BE TILL MATERIAL SHALL CONSIST OF AT LEAST

PRUNE SHRUBS AT OWNER'S DIRECTION.

/3 NATIVE SOIL FROM THE HOLE DUG FOR

1/3 NATIVE SOIL FROM THE HOLE DUG FOR THE PLANT. SEE SPECIFICATIONS FOR

BACKFILL MIXTURE.


THE PLANT. SEE SPECIFICATIONS FOR

BACKFILL MIXTURE.

BUILD 4"-6" CONTINUOUS SAUCER AROUND 2"X 4"X 24" STAKE (PRESSURE TREATED ROOT BALLS GREATER THAN 2-0" IN DIAM. SHALL SIT ON MOUND OF UNDISTURBED SOIL TO PREVENT SETTLING, ROOT BALLS SMALLER THAN 2'-O' DIAM, MAY SIT ON DIAMETER OF HOLE FOR BALL TO 2-0' SHALL BE TWICE THE DIAMETER OF THE ROOTBALL, DIAMETER OF THE HOLE FOR ROOTBALLS 2-0' & GREATER SHALL BE 2-0' LARGER THAN THE DIAM, OF THE BALL,

ILL MATERIAL SHALL CONSIST OF AT LEAST /3 NATIVE SOIL FROM THE HOLE DUG FOR THE PLANT. SEE SPECIFICATIONS FOR BACKFILL MIXTURE.

Irregular and Multi-/tem Tree




Typical Planter Sediment Filtration Detail

are not products of design. All ideas, designs, arrangements and plans indicated or represented by this/these drawings are owned by and the property of the designer, and were created, evolved and developed indemnify and hold harmless ENVIRONMENT for use on and in connection with this project. None of such ideas, designs, arrangements or plans shall be used by or disclosed to any person, firm or corporation without the written permission


of the Landscape Architect.

services during construction by the client, and his/her agents, employees, or subcontractors.





Shrub Planting



Shrub & Groundcover Layout

Palm Tree Planting

COA 23-43

Planting Motes

COMMERCIAL FERTILIZER:

FERTILIZER SHALL BE COMPLETELY ORGANIC, IT SHALL BE UNIFORM IN COMPOSITION, DRY AND FREE FLOWING. THIS FERTILIZER SHALL BE DELIVERED TO THE SITE IN THE ORIGINAL UNOPENED BAGS, EACH BEARING THE MANUFACTURER'S STATEMENT OF ANALYSIS, AND SHALL MEET THE FOLLOWING REQUIREMENTS:

SIX PERCENT (6%) NITROGEN SIX PERCENT (6%) PHOSPHOROUS SIX PERCENT (6%) POTASSIUM

FERTILIZER SHALL BE APPLIED TO ALL SHRUBS (1/3 LB. PER 3 GAL. POT, 1/4 LB. PER 1 GAL. POT) AND GROUNDCOVER. THE SAME FERTILIZER MIXTURE SHALL BE USED ON SOD AT A RATE OF 15 LBS. PER 1000 SQUARE FEET. A FOURTEEN PERCENT (14%) NITROGEN, FOURTEEN PERCENT (14%) PHOSPHOROUS AND FOURTEEN PERCENT (14%) POTASSIUM IS REQUIRED ON ALL TREES AND SHRUBS OVER 5'-O" IN HEIGHT (1/2 LB. PER 5'-O" OF SPREAD). AGRIFORM TABLETS WITH TWENTY PERCENT (20%) NITROGEN, TEN PERCENT (10%) PHOSPHOROUS, FIVE PERCENT (5%) POTASSIUM IN 21 GRAM SIZES SHALL BE APPLIED ALONG WITH THE FERTILIZER PROCESS (I WITH I GAL. PLANTS, 2 WITH 3 GAL. PLANTS AND 2 TABLETS PER I" OF TREE TRUNK CALIPER). BACK FILL HALFWAY UP THE ROOT BALL. PLACE ABOUT ONE INCH (I") FROM ROOT TIPS. MAGNESIUM SULFATE SHALL BE APPLIED TO ALL PALMS AT INSTALLATION AT A RATE OF 1/2 LB. PER INCH OF TRUNK CALIPER. MANGANESE SHALL BE APPLIED AT THE SAME RATE.

MULCH:

MULCH MATERIAL SHALL BE SHREDDED CYPRESS MULCH OR APPROVED EQUAL, MOISTENED AT THE TIME OF APPLICATION TO PREVENT WIND DISPLACEMENT. MULCH SHALL BE APPLIED TO A MINIMUM 3" DEPTH

THE SOD SHALL BE FREE FROM WEEDS, FUNGUS, INSECTS AND DISEASES OF ANY KIND, CLEAN, STRONGLY ROOTED, UNIFORMLY SIZED STRIPS, MACHINE STRIPPED NOT MORE THAN TWENTY-FOUR (24) HOURS PRIOR TO LAYING.

JUB/TITUTION/:

NO SUBSTITUTION OF PLANT MATERIAL TYPES OR SIZES WILL BE ALLOWED WITHOUT WRITTEN AUTHORIZATION FROM THE OWNER. CONTAINER GROWN MATERIAL WILL NOT BE ACCEPTED AS SUBSTITUTE FOR BEB MATERIAL UNLESS PREVIOUSLY APPROVED. INTENDED SUBSTITUTIONS SHALL BE SPELLED OUT IN BID.

MEA/UREMENT/:

HEIGHT SHALL BE MEASURED FROM GROUND TO THE AVERAGE BRANCH HEIGHT OF CANOPY. SPREAD SHALL BE MEASURED TO THE END OF THE BRANCHING EQUALLY AROUND THE CROWN FROM THE CENTER OF THE TRUNK. MEASUREMENTS ARE NOT TO INCLUDE ANY TERMINAL GROWTH. SINGLE TRUNK TREES SHALL BE FREE OF "V" CROTCHES THAT COULD BE POINTS OF WEAK LIMB STRUCTURE OR DISEASE INFESTATION.

HEIGHT SHALL BE MEASURED FROM THE GROUND TO THE AVERAGE POINT WHERE MATURE PLANT GROWTH STOPS. SPREAD SHALL BE MEASURED TO THE END OF BRANCHING EQUALLY AROUND THE SHRUB MASS. MEASUREMENT AREA NOT TO INCLUDE ANY TERMINAL GROWTH.

CLEAR TRUNK (C.T.) - SHALL BE MEASURED FROM THE GROUND AT TIME OF INSTALLATION TO THE POINT WHERE THE MATURE AGED TRUNK JOINS THE IMMATURE OR GREEN PORTION OF THE TRUNK OR HEAD.

> OVERALL HEIGHT (O.A.) - SHALL BE MEASURED FROM THE GROUND AT THE TIME OF INSTALLATION TO THE AVERAGE FROND HEIGHT.

PALMS WITH MARRED OR BURNED TRUNKS WILL NOT BE ACCEPTED.

PLANTING / OIL AND BACKFILL:

PLANTING SOIL FOR USE IN PREPARING BACKFILL FOR PLANT PITS SHALL BE A FERTILE, FRIABLE AND NATURAL TOPSOIL, WITHOUT MIXTURE OF SUBSOIL MATERIALS, AND SHALL BE FREE FROM HEAVY CLAY, STONES, LIME, LUMPS, SHELLS, PLANTS, ROOTS OR OTHER FOREIGN MATERIALS, WEEDS, OR NOXIOUS GRASSES (SUCH AS BERMUDA OR NUT GRASS). IT SHALL NOT CONTAIN TOXIC SUBSTANCES WHICH MAY BE HARMFUL TO THE PLANT GROWTH.

BACKFILL FOR SOD AREAS SHALL BE SUBJECT TO LESSER STANDARDS AT THE DISCRETION AND DECISION OF THE OWNER.

EXISTING TOPSOIL SHALL BE USED IN ALL PLANT MATERIAL PITS EXCEPT SABAL PALMS WHERE THE SOIL SHALL CONSIST OF CLEAN SAND.

PLANTING SOIL FOR USE IN BEDS FOR ANNUALS AND/OR PERENNIALS SHALL CONTAIN ONE-THIRD (1/3) POTTING SOIL OR A BLENDED TOPSOIL, TILL INTO TOP 10" - 12" OF SOIL WITH A TIME-RELEASE FERTILIZER.

PLANT MATERIALS:

PALMS, TREES, SHRUBS, GROUNDCOVERS AND VINES

PLANT SPECIES AND SIZE SHALL CONFORM TO THOSE INDICATED ON THE DRAWINGS. NOMENCLATURE SHALL CONFORM TO "STANDARDIZED PLANT NAMES", 1942 EDITION. ALL NURSERY STOCK SHALL BE IN ACCORDANCE WITH "GRADES AND STANDARDS FOR NURSERY PLANTS PARTS I & II", LATEST EDITION PUBLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUMER SERVICES. UNLESS SPECIFIED OTHERWISE, ALL PLANTS SHALL BE FLORIDA GRADE NUMBER I OR BETTER AS DETERMINED BY THE FLORIDA DIVISION OF PLANT INDUSTRY. SPECIMEN MEANS AN EXCEPTIONALLY HEAVY, SYMMETRICAL TIGHTLY KNIT PLANT, SO TRAINED OR FAVORED IN ITS DEVELOPMENT THAT FIRST APPEARANCE IS UNQUESTIONABLE AND OUTSTANDINGLY SUPERIOR IN FORM, NUMBER OF BRANCHES, COMPACTNESS AND SYMMETRY. ALL PLANTS SHALL BE FRESHLY DUG, SOUND, HEALTHY, VIGOROUS, WELL BRANCHED AND FREE OF DISEASE AND INSECT EGGS AND LARVAE AND SHALL HAVE ADEQUATE ROOT SYSTEMS. TREES FOR PLANTING ROWS SHALL BE UNIFORM IN SIZE AND SHAPE. ALL MATERIALS SHALL BE SUBJECT TO APPROVAL BY THE OWNER. WHERE REQUIREMENTS ARE OMITTED FROM THE PLANT LIST, THE PLANTS FURNISHED SHALL BE NORMAL FOR THE VARIETY AND FLORIDA NUMBER I. PLANTS SHALL BE PRUNED PRIOR TO DELIVERY ONLY UPON THE APPROVAL OF THE OWNER.

CONTAINER GROWN / TOCK:

- ALL CONTAINER GROWN MATERIAL SHALL BE HEALTHY, VIGOROUS, WELL-ROOTED PLANTS AND ESTABLISHED IN THE CONTAINER IN WHICH THEY ARE SOLD. THE PLANTS SHALL HAVE TOPS OF GOOD QUALITY AND BE IN A HEALTHY GROWING CONDITION.
- AN ESTABLISHED CONTAINER GROWN PLANT SHALL BE TRANSPLANTED INTO A CONTAINER AND GROWN IN THAT CONTAINER SUFFICIENTLY LONG ENOUGH FOR THE NEW FIBROUS ROOTS TO HAVE DEVELOPED SO THAT THE ROOT MASS WILL RETAIN ITS SHAPE AND HOLD TOGETHER WHEN REMOVED FROM THE

WARRANTY:

WARRANTY PLANTS, SHRUBS AND GROUNDCOVERS FOR A PERIOD OF NINETY (90) DAYS: TREES & PALMS FOR ONE YEAR (1) AGAINST UNHEALTHY CONDITION, EXCEPT AS MAY RESULT FROM NEGLECT BY OWNER, DAMAGE BY OTHERS, AND UNUSUAL PHENOMENA BEYOND INSTALLER'S CONTROL. REPLACE AT TIME REQUESTED BY THE OWNER OR LANDSCAPE ARCHITECT.

MAINTENANCE:

MAINTAIN LANDSCAPE WORK UNTIL THE LETTER OF SUBSTANTIAL COMPLETION BY THE GENERAL CONTRACTOR. INCLUDE WATERING, WEEDING, CULTIVATING, RESTORATION OF GRADE, MOWING AND TRIMMING GRASS, PRUNING TREES AND SHRUBS, PROTECTION FROM INSECTS AND DISEASES, FERTILIZATION AND SIMILAR OPERATIONS AS NEEDED TO ENSURE NORMAL GOOD HEALTH FOR LIVE

DE/IGN ROUP 139 North County Road S#20-B Palm Beach, FI 33481 Mobile 561.313.4424 Phone 561.832.4600

Landscape Architecture Land Planning Landscape Management Dustin M. Mizell, MLA RLA #6666784

Dustin@environmentdësiqnqroup.com

• S

JOB NUMBER: 21089.00 LA DRAWN BY: Dustin Mizell

DATE:

ZON-23-117 Planting Details & Specifications