



TOWN OF PALM BEACH
Planning, Zoning & Building Department
360 South County Road
Palm Beach, FL 33480
(561) 838-5431 • www.townofpalmbeach.com

PLANNING, ZONING, & BUILDING DEPARTMENT
PZ&B Staff Memorandum: Architectural Commission (ARCOM)

FROM: Wayne Bergman, MCP, LEED-ARB
Director PZ&B

SUBJECT: ARC-24-0034 (ZON-24-0020) 336 AUSTRALIAN AVE W

MEETING: AUGUST 28, 2024

ARC-24-0034 (ZON-24-0020) 336 AUSTRALIAN AVE W (COMBO) - VARIANCES. The applicant, Sharon Handler Loeb, has filed an application requesting Architectural Commission review and approval for site wide landscape and hardscape modifications, installation of a generator and the relocation of pool equipment requiring variances. Town Council shall review the application as it pertains to zoning relief/approval.

ZON-24-0034 (ARC-24-0020) 336 AUSTRALIAN AVE W (COMBO) – VARIANCES. The applicant, Sharon Handler Loeb, has filed an application requesting Town Council review and approval of three (3) variances to (1) not providing minimum required landscaped open space, (2) to allow pool equipment and generator to be installed without the minimum required setback and (3) pool equipment located further than the maximum of 25 feet from water's edge. The Architectural Commission (ARCOM) shall perform design review of the application.

Applicant: Sharon Handler Loeb
Professional: Environment Design Group

HISTORY:

The application was presented at the July ARCOM meeting and received partial approval. During the hearing, the adjacent homeowner attended and voiced concerns regarding the proposed changes on the north and east sides of the property, which directly impact their residence. The Commission voted 6-0 in favor of the application, contingent upon the condition that the landscape design for the north and east sides be reviewed by the Chairman after an agreement between both parties had been reached. However, due to the inability to find a mutually acceptable landscape design, the design professional has resubmitted the application for consideration at the August 28, 2024, ARCOM meeting.

THE PROJECT:

The applicant has submitted plans, entitled "336 W Australian Avenue" as prepared by **Environment Design Group**, uploaded August 5, 2024, and identified as final submittal for ARCOM hearing 8/25/24.

The following scope of work is proposed:

- Modification to entry courtyard.
- Relocation of pool equipment with installation of a pool heater and generator.

- Addition of privacy wall with landscape improvements.


The following is required to complete the project:

1. **VARIANCE 1: Section 134-948:** Landscape Open Space = 45% (For single-family uses, the minimum landscaped open space is 45 percent, of which 50 percent of that percentage is required to be perimeter landscaping within ten feet of the property line)
2. **VARIANCE 2 & 3: Section 134-1728(c) (1)**Swimming pool and fountain pump and filter equipment shall have a minimum five foot side and rear yard setback and shall in all situations be located no further than 25-feet from the pool or fountain water's edge.(2)Swimming pool heater equipment shall have a minimum ten-foot side and rear yard setback and shall in all situations be located no further than 25-feet of the swimming pool water's edge.

Site Data			
Zoning District	R-C	Future Land Use	SINGLE-FAMILY
Lot Size	Required: 10,000 SF Existing: 6,252 SF	Lot Coverage	Existing: 2,238 SF Proposed: No Change
Lot Depth	Existing: 125'	Lot Width	Existing: 50'
Overall Landscape Open Space	Required: 45% Existing: 26.74% Proposed: 36.35	Native Landscape	Trees: 83% Groundcover: 32.35% Shrubs & Vines: 31.82%
Perimeter Landscape Open Space	Required: 50% Existing: 54.14% Proposed: 60.25	Front Yard Landscape Open Space	Required: 40% Existing: 54.56% Proposed: 51.28
Surrounding Properties / Zoning			
North	353 Coconut Row Condominium / R-C		
South	347 Chilean Ave Single-family Residence/ R-C		
East	336 Australian Ave – East Single-Family Residence / R-C		
West	363 Coconut Row Hotel / R-C		



PROPOSED SITE PLAN RENDERING



STAFF ANALYSIS

The applicant is proposing renovations to hardscape and landscape to half of an attached duplex parcel, including the relocation of mechanical and pool equipment, which will require variances related to setback and distance separations.

Code Section	Required	Proposed	Variance
<u>Variance 1:</u> Section 134-948	45% overall open space	36.35% LOS	8.65%
<u>Variance 2:</u> Section 134-1728(c)	Pool equipment @ 25'	54'-2"	29'-2"
<u>Variance 3:</u> Section 134-1728(c)	10' setback pool heater	3'	7'

Additionally, the applicant is proposing to modify more than 50% of the existing landscape open

space area. The zoning code requires that landscape open space calculations be brought up to current requirements if altering 50% of the existing landscape area. Although the applicant is proposing an improvement from existing conditions (36.35% proposed in lieu of the 26.74% existing), a variance is required for failure to meet the 45% minimum required. Although the applicant is proposing an improvement from existing conditions (36.35% proposed in lieu of the 26.74% existing), a variance is required for failure to meet the 45% minimum landscape open space required.

The proposed pool equipment location is within the required setback (variance #3) and spaced further than permitted from the edge of the water (variance #2).

CONCLUSION:

Approval of the project will require two (2) separate motion(s) to be made by the Architectural Commission:

1. for the overall design of the project in accordance with [Sec. 18-205](#) criteria, subject to any imposed conditions, and
2. that the implementation of the proposed variances **will** or **will not** cause negative architectural impacts to the subject property.

Approval of the project will require one (1) motion to be made by the Town Council:

1. for final determination of approval or denial of the variance by the Town Council, and that the variance **shall** or **shall not** be granted that all the criteria applicable to this application as set forth in [Sec. 134-201\(a\)](#), items 1 through 7 have been met.

WRB:JGM:SCP