

COSTON MARINE SERVICES, INC.

228 Hibiscus Street, Suite 4
Jupiter, FL 33458
Office: 561-747-4382 Fax: 561-745-2387
Email: costonmarine@gmail.com

Town of Palm Beach
951 Okeechobee Road
West Palm Beach, Fl. 33401
Attn: Robert Weber
Email: rweber@townofpalmbeach.com
P-561-838-5440

August 21, 2018

Change Order 3: Additional Rock Excavation: North Waterway Segment

Project No.: 2016-28

Project Name: "Lake Worth Lagoon Waterway Access Maintenance Dredging"

Scope of Work

(Dredging of Solid

Rock Layer from Station 66+40 to Station 68+20)

1. Mobilize larger excavator with rock bucket to site. **No charge for this item, already in previous change order.**
2. Mechanically dredge approximately **600 cubic yards** of solid rock dredge spoil material from Station 66+40 to Station 67+40 which is 4' thick to the permitted designed depth including 1' over dredge. Also dredge approximately **250 cubic yards** of solid rock dredge spoil material from Station 67+40 to Station 68+20 which starts with a 4' thick rock layer that tapers down to the design grade after about 80'. The channel cut will be 40' wide minimum for this section. The remaining channel and the turning basin should be normal dredging as per main contract. This rate is based on added time it takes to dig through the rock layer, added time in moving, as well as added wear and tear on equipment. We are estimating that this section of rock digging will take about 35-40 days based on no equipment breakdown and unforeseen weather events or forced shutdowns.

Price Add

The total added cost based on the above will be **\$ 85,000.00.**

SUBMITTED:

Michael Bryant

ACCEPTED:

Michael Bryant
Coston Marine Services, Inc.

Owner

Date